

- GENERAL NOTES**
1. RUN ALL AIR, GAS & WATER LINES TIGHT TO THE UNDERSTANDING OF BEARS.
 2. GAS FIRED UNIT HEATER #2 1/2" FLUE UP THRU ROOF 1/2" CAP (SEE DETAIL THIS SHEET & SCHEDULE ON H-1).
 3. GAS FIRED UNIT HEATER #1 1/2" FLUE UP THRU ROOF 1/2" CAP (SEE DETAIL THIS SHEET & SCHEDULE ON H-1).
 4. 3/8" AIR LINE DOWN COLUMN TO 3'-0" ABOVE FLOOR & TERMINATE W/AIR VALVE AND CAP.
 5. 1/2" WATER LINE DOWN COLUMN TO 3'-0" ABOVE FLOOR W/HOSE BIBB AND VACUUM BREAKER.

