

**Frederick County Compost Pad Resurfacing
Bid Form**

Item No.	Description	Unit	Unit Cost/Rate	Est. Quantity	Total Cost
General					
1	Mobilization	LS		1	\$ -
2	Demobilization	LS		1	\$ -
3	Contractor Staging area Maintenance	LS		1	\$ -
Erosion & Sediment Controls					
4	Stabilized Construction Entrances	LS		2	\$ -
5	Silt Fence	LF		400	\$ -
6	Temporary Stabilized Construction Access Ramps	LS		3	\$ -
7	Furnish and Install Inflow Protection Riprap for 3 Existing Downchutes	Tons		300	\$ -
8	Post-Construction Stabilization of Disturbed Vegetated Areas - Seeding and Mulching	LS		1	\$ -
9	Erosion and Sediment Control Measures Not Otherwise Itemized	LS		1	\$ -
Staged Construction					
10	Remove and Stockpile Millings from Operations Pad	CY		2,900	\$ -
11	Prepare Operations Pad Surface for Resurfacing	SF		222,100	\$ -
12	Furnish and Install Materials for High-Traffic Pavement Sections				\$ -
	<i>Tensar NX850 Geogrid</i>	<i>SF</i>		<i>95,260</i>	<i>\$ -</i>
	<i>Graded Aggregate</i>	<i>CY</i>		<i>6,472</i>	<i>\$ -</i>
	<i>Asphalt Base Course</i>	<i>CY</i>		<i>1,177</i>	<i>\$ -</i>
	<i>Tack Coat (2 applications)</i>	<i>SF</i>		<i>190,520</i>	<i>\$ -</i>
	<i>Asphalt Surface Course</i>	<i>CY</i>		<i>883</i>	<i>\$ -</i>
13	Furnish and Install Materials for Low-Traffic Pavement Sections				\$ -
	<i>Tensar NX850 Geogrid</i>	<i>SF</i>		<i>126,840</i>	<i>\$ -</i>
	<i>Graded Aggregate</i>	<i>CY</i>		<i>8,617</i>	<i>\$ -</i>
	<i>Asphalt Base Course</i>	<i>CY</i>		<i>1,175</i>	<i>\$ -</i>
	<i>Tack Coat (2 applications)</i>	<i>SF</i>		<i>253,680</i>	<i>\$ -</i>
	<i>Asphalt Surface Course</i>	<i>CY</i>		<i>783</i>	<i>\$ -</i>
14	Furnish and Install Topsoil for Raising Perimeter Containment Berm	CY		420	\$ -
15	Provide Traffic Control for Staged Construction	LS		1	\$ -
TOTAL					\$ -

Notes:

- Quantities in this Bid Form are Engineer's Estimates. Project Work Scope is described in IFB and illustrated on Project Drawings. Bidders shall verify quantities and establish a unit price for each item identified in the Bid Form by submitting a bid. Bidder accepts that the entire Project Work Scope, including temporary measures and protection of the Work, will be accomplished by performing line items and quantities in Bid Form.
- Contractor to furnish all materials to complete the project. Owner will not provide any materials, unless specifically stated in the IFB.